



APPROXIMATE COST OF 1274 LIN. FT. OF
S. W. 29TH ST. WIDENING IMPROVEMENT

4,587	Sq. Yds.	Asphalt Surface	-----	@ \$1.00 =	\$4,587.00
2,159	"	"	Base Course	-----	@ 1.00 = 2,159.00
160	Cu. Yds.	Gravel	-----	@ 5.00 =	800.00
108	"	"	Sand, Stabilization for Subgrade	@ 3.00 =	324.00
566	"	"	Unclassified Excavation	@ 0.70 =	396.20
2428	Lin. Ft.	Conc. Curb & Gutter	-----	@ 1.25 =	3,035.00
250	Sq. Yds.	Asphalt Jacking & Pumping	-----	@ 0.50 =	125.00
TOTAL =					\$11,426.20

BASE WIDENING
AND 3" ASPHALTIC CONCRETE SURFACE

19,947	Sq. Yds.	Asphalt Surface	-----	@ \$1.00 =	\$19,947.00
9,387	"	"	Base Course	-----	@ 1.00 = 9,387.00
722	Cu. Yds.	Gravel	-----	@ 5.00 =	3,610.00
470	"	"	Sand for Subgrade Stabilization	@ 3.00 =	1,410.00
2264	"	"	Unclassified Excavation	@ 0.30 =	679.20
2000	Sq. Yds.	Asphalt Jacking & Pumping	-----	@ 0.50 =	1,000.00
Cost Per Mile For 34 F.T. Section					TOTAL = 36,033.20
Cost Per Mile For 44 F.T. Section					\$51,783.00

APPROXIMATE COST PER MILE
TO WILL ROGERS AIR FIELD